

**DISTRIBUTION SCHEDULE
DUCHESNE – STRAWBERRY RIVER**

DESCRIPTIONS OF DISTRIBUTION ZONES

For the purposes of this Distribution Schedule, the Duchesne – Strawberry River System is divided into three zones which are described as follows:

ZONE I

Zone I includes the lands irrigated between the headwaters of the Duchesne River and the bridge (locally known as the Williams Bridge) on State Route 35 just above the confluence of Rock Creek with the Duchesne River. Zone I also includes the lands irrigated between the headwaters of Red Creek and its confluence with the Strawberry River, excluding Currant Creek.

ZONE II

Zone II includes the lands irrigated between the bridge (locally known as Williams Bridge) on State Route 35 just above the confluence of Rock Creek and the Duchesne River and down to the confluence of the Strawberry River with the Duchesne River.

ZONE III

Zone III includes all the lands irrigated below the confluence of the Strawberry River with the Duchesne River including Indian Canyon.

DELIVERY SCHEDULES

ZONE I

Either Delivery Schedule A or Delivery Schedule B (both shown below) may be used for the distribution of water in Zone I. The Duchesne River Commissioner will determine which schedule should be used for the current year depending upon the climatic conditions existing in Zone I.

ZONE II

Either Delivery Schedule B or Delivery Schedule C (both shown below) may be used for the distribution of water in Zone II. The Duchesne River Commissioner will determine which schedule should be used for the current year depending upon the climatic conditions existing in Zone II.

III

Delivery Schedule C (shown below) shall be used for the distribution of water in Zone III.

DELIVERY SCHEDULE "A"

May 1 – October 15, 4.0 Acre-Feet per Acre

<u>PERIOD</u>			<u>DUTY</u>		<u>DELIVERY</u>	
Date (1)	No. of Days (2)		CFS/Acres (3)	AF/Day (4)	AF/Period (5)	Accum AF (6)
May 1-15	15		1/100	0.01983	0.298	0.30
May 16-31	16		1/60	0.03306	0.529	0.83
June 1-15	15		1/60	0.03306	0.496	1.32
June 16-30	15		1/65	0.03051	0.458	1.78
July 1-15	15		1/70	0.02834	0.425	2.21
July 15-31	16		1/80	0.02479	0.397	2.60
Aug. 1-15	15		1/80	0.02479	0.372	2.98
Aug. 16-31	16		1/85	0.02333	0.373	3.35
Sept. 1-15	15		1/100	0.01983	0.298	3.65
Sept. 16-30	15		1/150	0.01322	0.198	3.84
Oct. 1-15	15		1/200	0.00991	0.149	3.99

DELIVERY SCHEDULE "B"

April 20 – October 15, 4.0 Acre-Feet per Acre

<u>PERIOD</u>			<u>DUTY</u>		<u>DELIVERY</u>	
Date (1)	No. of Days (2)		CFS/Acres (3)	AF/Day (4)	AF/Period (5)	Accum AF (6)
Apr. 20-30	11		1/145	0.01368	0.150	0.15
May 1-15	15		1/100	0.01983	0.298	0.45
May 16-31	16		1/85	0.02333	0.373	0.82
June 1-15	15		1/60	0.03306	0.496	1.32
June 16-30	15		1/65	0.03051	0.458	1.78
July 1-15	15		1/70	0.02834	0.425	2.21
July 15-31	16		1/80	0.02479	0.397	2.60
Aug. 1-15	15		1/80	0.02479	0.372	2.98
Aug. 16-31	16		1/85	0.02333	0.373	3.35
Sept. 1-15	15		1/100	0.01983	0.298	3.65
Sept. 16-30	15		1/150	0.01322	0.198	3.85
Oct. 1-15	15		1/200	0.00991	0.149	4.00

DELIVERY SCHEDULE "C"

April 1 – October 15, 4.0 Acre-Feet per Acre

<u>PERIOD</u>			<u>DUTY</u>		<u>DELIVERY</u>	
Date (1)	No. of Days (2)		CFS/Acres (3)	AF/Day (4)	AF/Period (5)	Accum AF (6)
April 1-15	15		1/160	0.01240	0.186	0.186
April 16-30	15		1/160	0.01240	0.186	0.186
May 1-10	10		1/125	0.01587	0.159	0.531
May 11-20	10		1/90	0.02204	0.220	0.751
May 21-31	11		1/80	0.02479	0.273	1.024
June 1-10	10		1/70	0.02834	0.283	1.307
June 11-20	10		1/70	0.02834	0.283	1.590
June 21-30	10		1/75	0.02645	0.265	1.855
July 1-10	10		1/75	0.02645	0.265	2.120
July 11-20	10		1/80	0.02479	0.248	2.368
July 21-31	11		1/80	0.02479	0.273	2.641
Aug. 1-15	15		1/80	0.02479	0.372	3.013
Aug. 16-31	16		1/85	0.02333	0.373	3.386
Sept. 1-15	15		1/100	0.01983	0.297	3.683
Sept. 16-30	15		1/150	0.01322	0.198	3.881
Oct. 1-15	15		1/250	0.00793	0.119	4.000