

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER Executive Director

Lieutenant Governor

Division of Water Rights KENT L. JONES

State Engineer/Division Director

February 21, 2013

RE:

Pc:

Stream Channel Alteration No. 13-43-03SA

Un-named

Duchesne County

Attached is a copy of an application to alter a natural stream, which has been submitted to the Division of Water Rights (Division) for processing.

In processing this application, the Division will work to determine if the project will:

- Unreasonably or unnecessarily affect any recreational use or the natural stream environment;
- Unreasonably or unnecessarily endanger aquatic wildlife;
- Unreasonably or unnecessarily diminish the natural channel's ability to convey high flows; or
- Impair vested water rights.

Any decision made regarding this application will be based exclusively on these four criteria. If you have information regarding these four criteria that will aid the Division in making a determination and subsequent decision, please submit this information, in writing, to this office prior to March 13, 2013. For questions or comments pertaining to all other aspects of the project, please contact the applicant listed on the front page of the application directly.

Sincerely,

Tiffany Jonzales Daren Rasmussen, P.G.

Stream Alteration Specialist

Richard Clark - EPA

Corps of Engineers

Supervisor - U. S. Fish & Wildlife

Bob Leake - Regional Engineer

Miles Hanberg - Regional Wildlife Habitat Manager

Carmen Bailey - Aquatic Habitat Coordinator

Bill Damery - DEQ, Water Quality Division

Laura Ault - Forestry Fire & State Lands

Kelly Beck - RDCC Coordinator

State Parks & Recreation

Lori Hunsaker - State History

W. D. Robinson - Department of Agriculture

Judy Watanabe - CEM



Rec. by Fee Rec. 4505 Receipt # 13-00074

JOINT PERMIT APPLICATION FORM

U.S ARMY CORPS OF ENGINEERS – FOR SECTIONS 404 AND 10 UTAH STATE ENGINEER'S OFFICE – FOR NATURAL STREAM CHANNELS

Applicant's Name (Last, First M.L. or entity if not an individual) Duchesne County Jones & DeMille Engineering, Inc. Applicant's Address (Streec, RFD, Box, Number, City, State, Zip) Duchesne County Special Service District #2 165 South Center, Duchesne, UT 84021 PROJECT LOCATION V: 4/4/31/9.97 Quarter Section(s) Section Township Range Quarter Section(s) Section Township Range Duchesne PROJECT LOCATION V: 4/4/31/9.97 Quarter Section(s) Section Township Range Duchesne Project location or address: Pariette Road, approx. 3.8 miles South from HWY 40; From Google Earth: 40° 08′ 11.30° N and 110° 05′ 35.88° W. Project Station 117+65 Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60° circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project The drainage and roadway improvements will generally improve drainage, increase capacity of culver system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. If shis a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project of other related activities. 113.2 CY of Riprap Material Areage or square forcage of waters of the U	Application Number			, 1	3-43-0351	4	
Duchesne County Jones & DeMille Engineering, Inc. Approximately 3, 36457783-1144 Project Including methods and equipment to be employed to complete the work. This culvert project is a part of a large roadway reconstruction project that includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below with standard exacavation equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (pusitification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culver system, enhance the roadway geometry to a reasonable and necessary level, and improve the coverall public safety and function of the roadway. Historic flooding of the roadway and adjacent propecties included in the County Road 33 Reconstruction project (see attached Location Map) and is included the discharge of drainage of roadway reconstruction project in construction of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dradged or fill material into a watercourse or wetland. Length of stream that will be impacted below ordinary high water elevation. Approximately 200 feet (168' pipe)	(assigned by):		Corps		State Engir	neer	
Associated Watercourse or Watercourse to be Altered With No. 11 October 1 October 2 October 1 October 2 O	Applicant's Name (Last, First M.I. or entity if not an individual)		Authorized Applicant Representative (if any)				
Duchesne County Special Service District #2 165 South Center, Duchesne, UT 84021 X: 57730.8	Duchesne County		Jones & DeMille Engineering, Inc.				
PROJECT LOCATION 244310.97							
Sw1/4 NE1/4 15 Associated Watercourse to be Altered Check one: Within City Limits Gourside City Limits County Associated Watercourse or Watercourse to be Altered Check one: Within City Limits Gourside City Limits Check one: Within City L							
SW1/4 NE1/4 15 4S 2W Uintah Country Associated Watercourse or Watercourse to be Altered Check one Within City Limits Outside City Limits Limits Without or nearest town. Myton, UT Wyton, UT Project location or address: Pariette Road, approx. 3.8 miles South from HWY 40; From Google Earth: 40° 08′ 11.30° N and 110° 05′ 35.88° W; Project Station 117+65 Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60° circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culver's system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland. Cubic yards of material: Acreage or square fottag					4443119.	97	
Duchesne Un-named Un-named Check one: Within City Limits Outside City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within or or places town: Myton, UT Check one: Within or or places tawn: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within or or places tawn: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: Within City Limits List town or nearest town: Myton, UT Check one: All 113.0 No and 110.0 A places described in the Check one places and in the Check of the United States affected by the project. Check one: All 113.0 Cy of Riprap Material Drainage Area = approx. 13,000 acres Engineer approved clean riprap stone Approximately 200 feet (168' pipe)				US.			US
Duchesne Un-named Myton, UT Project location or address: Pariette Road, approx. 3.8 miles South from HWY 40, From Google Earth: 40° 08' 11.30° N and 110° 05' 35.88° W; Project Station 117+65 Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culverd system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the United States affected by the project: Source and type of fill material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	SW1/4 NE1/4	15	45	200		Uintan	
Project location or address: Pariette Road, approx. 3.8 miles South from HWY 40; From Google Earth: 40° 08' 11.30" N and 110° 05' 35.88" W; Project Station 117+65 Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. If project included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	County	Assoc	ciated Watercourse or Watercours		the late of the second	mits Outside City	Limits
Project location or address: Pariette Road, approx. 3.8 miles South from HWY 40; From Google Earth: 40° 08' 11.30" N and 110° 05' 35.88" W; Project Station 117+65 Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities? The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	Duchesne Un		10 0 100 0 0				
Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	Project location or address:	1			,		
Brief description of project including methods and equipment to be employed to complete the work: This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	Pariette Road, approx 3.8	miles South from	HWY 40: From Google Fart	th: 40° 08' 11.30" N a	and 110° 05' 35.88"	W: Project Statio	n 117+65
This culvert project is a part of a large roadway reconstruction project that includes multiple drainage improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culverd system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
improvements. This location will replace an existing culvert that has a history of plugging and being undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culverd system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	This culvert project	is a part of a	large roadway recor	struction project	ct that includes	multiple dra	inage
undersized for large storm events. The proposed drainage structure includes four 60" circular pipes with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	improvements This	location will	replace an existing	culvert that has	a history of pl	ugging and b	peina
with concrete headwalls and wingwalls, with riprap placed below the downstream outlet. Pipe will be installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
installed with standard excavation equipment including trackhoe/backhoe, front end loader, and compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	undersized for large	storm event	s. The proposed dra	inage structure	includes lour	ou circular	pipes
compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culvert system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
compaction equipment. Concrete will be formed and cast-in-place in dry conditions. Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culver system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	installed with standa	ard excavatio	n equipment includir	ng trackhoe/bac	khoe, front en	d loader, and	b
Purpose (justification) of project: The drainage and roadway improvements will generally improve drainage, increase capacity of culver system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	compaction equipm	ent. Concret	e will be formed and	cast-in-place in	n dry condition	S.	
system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
system, enhance the roadway geometry to a reasonable and necessary level, and improve the overall public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)			vements will genera	ally improve dra	inage increas	e capacity of	f culver
public safety and function of the roadway. Historic flooding of the roadway and adjacent properties in this location is justification for replacement of existing culverts prior to reconstruction of the roadway. Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
Is this a single and complete project or is part of a larger project, continuing project, or other related activities? If so, please describe the larger project or other related activities. The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	this location is justif	ication for rep	placement of existing	culverts prior	to reconstruction	on of the roa	dway.
The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							
The project is included in the County Road 33 Reconstruction project (see attached Location Map) and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)		oject or is part of a lar	ger project, continuing project, or	other related activities?	If so, please describe th	e larger project or ot	her related
and is to be installed as part of the drainage improvements prior to roadway reconstruction. If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)		ded in the Co	unty Road 33 Recon	struction project	ct (see attache	d Location M	(ap)
If project included the discharge of dredged or fill material into a watercourse or wetland: Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)							(ap)
Cubic yards of material: Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Acreage or square footage of waters of the United States affected by the project: Drainage Area = approx. 13,000 acres Engineer approved clean riprap stone Approximately 200 feet (168' pipe)					caunay recon		
Acreage or square footage of waters of the United States affected by the project: Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Drainage Area = approx. 13,000 acres Engineer approved clean riprap stone Approximately 200 feet (168' pipe)		of diedged of fill ma	neriai ilito a watercourse or wetta			G	
Source and type of fill material: Length of stream that will be impacted below ordinary high water elevation: Engineer approved clean riprap stone Approximately 200 feet (168' pipe)							013
Length of stream that will be impacted below ordinary high water elevation: Approximately 200 feet (168' pipe)	Acreage or square footage of waters of the United		States affected by the project:				
Approximately 200 feet (100 pips)	Source and type of fill mate	rial:		Engineer app	noved clean n	prap storie	- 69
passa: Lukeo	Length of stream that will b	e impacted below ord	linary high water elevation:	Approximate	ly 200 feet (16	8' pipe)	E E
						793	

Alternatives (other ways to accomplish project purpose):	
	would maintain functionality and safety of the public
Describe any proposed mitigation to offset impacts to the stream char	nnel.
channel and protect from scour during high	led downstream of culverts to direct flow into original h flows. No further bank stabilization measures will be intermittent, with flows occurring after storm events, snow
Cultural resource impacts:	
Are you aware of any cultural resources or any historic properties that If Yes, please explain:	at will be impacted by the proposed project? □ Yes \ No
Has a cultural resource survey been conducted on the property where If Yes, please briefly explain the survey results:	the proposed project is to occur?
List other authorizations required by Federal, state, or local government	ents (i.e.: National Flood Insurance Program), and the status of those authorizations.
Estimated starting date of project:	Estimated completion date:
March 29, 2013	September 1, 2013
Please con	nnlete the following checklist

Failure to indicate that all pertinent information has been submitted will result in your application being returned.

- Appropriate application processing fee payment (see fee schedule below).
- A clear site location map with enough detail to easily find the site, a recent aerial/satellite image of the site, and a USGS topography map (7.5 minute quadrangle map is recommended).
- Plan view and cross-sectional drawings showing all work requiring a permit, including fills, structures, borrow sites, staging areas and storage areas. The drawings must clearly demarcate the ordinary high water mark of the waters of the U.S. to be impacted. Professional drawings are not required; however, drawings must be scaled or indicate dimensions of the work to be completed.
- A restoration plan for any areas temporarily disturbed during work, including re-contouring, revegetation with appropriate native plants and maintenance and monitoring to ensure success for the restored area.
- Ground photographs taken from various locations of the proposed disturbance area.
- Please check the box if the proposed project involves bank stabilization or protection. If so, please complete the following:
 - A narrative demonstrating the proposed activity incorporates the least damaging bank protection methods. These methods include, but are not limited to, the use of bioengineering, biotechnical design, root wads, large woody debris, native plantings, and beach nourishment in certain circumstances. If rock must be used due to site erosion conditions, explain how the bank stabilization structure incorporates elements beneficial to aquatic organisms.

- A description of current and expected post-activity sediment movement and deposition patterns in and near the activity area.
- A description of current and expected post-activity habitat conditions, including the presence of fish, wildlife and plant species in the activity area.
- An assessment of the likely impact the work would have on upstream, downstream and cross-stream properties (at a minimum the area assessed should extend from the nearest upstream bend to the nearest downstream bend of the watercourse). Specifically, discuss how the project will impact the following:

Will the activity accelerate deposition or erosion?

Will impacts to sensitive species or habitats result from a change in suspended sediment load or turbidity? Will the activity affect the diversity of the channel by eliminating in-stream habitat, meanders, or gravel bars?

Will the activity result in a shift in the main flow patterns?

A planting plan which involves the use of native riparian plants, unless the applicant demonstrates it is not appropriate or not practicable.

Application is hereby made for a permit or permits to authorize the activities described herein. I certify that I am familiar with the information contained in the application, and that to the best of my knowledge and belief, such information is true, complete and accurate. I further certify that I possess the authority to undertake the proposed activities or am acting as the duly authorized agent of the applicant which is a (check one of the following) commercial \(\subseteq \), non-commercial \(\supseteq \), or governmental entity.

Signature of Applicant

Date: 2-13-2013

I hereby certify that Jones and DeMille Engineering (Michael Hawley) is acting as my agent on this project.

Agent's address and telephone number: 187 West Lagoon Street (45-13) Roosevelt UT 84066 Phone: 435.722.8267


Filing Instructions

Application supplements should be submitted on paper no larger than 11 x 17 inches or alternatively as PDF format electronic files. If more than one watercourse is to be altered as a result of the project, a separate application must be submitted for each watercourse. Application fees must be received by the Division of Water Rights at the time of application submission and must be either hand delivered or submitted through standard mail.

Application Processing Fees

Application fees are based on the type of entity applying for the proposed stream alteration project.

Commercial Entities: \$2000.00 per application processed. Non-Commercial Entities: \$100.00 per application processed. Governmental Entities: \$500.00 per application processed.



www.jonesanddemille.com

TRANSMITTAL

DATE: February 5, 2013

TO: Department of Natural Resources

Division of Water Rights

1594 West North Temple, Suite 220 Salt Lake City, UT 84114-6300

ATTENTION: Daren Rasmussen

PROJECT: Duchesne County Special Service District #2 – County Road 33 Reconstruction

PROJECT NO.: 1112-027

ENCLOSED PLEASE FIND THE FOLLOWING:

Stream Alteration Permits (2) - Wells Draw STA 95+50 and Un-Named Stream STA 117+65

REMARKS:


Please find the attached Joint Permit Application Forms with associated Location Maps, Details, and Photos sheets. Feel free to contact Michael Hawley at Jones and DeMille Engineering at 435.722.8267 or by email at michael@jonesanddemille.com.

Thank you.

BY: Michael Hawley, PE

cc: Carrie Mascaro, Duchesne SSD #2






PROJECT LOCATION MAP

PIPE CULVERTS ON UN-NAMED INTERMITTENT STREAM APPLICANT: DUCHESNE COUNTY SHEET NO. 1

SEC. 15, T. 4S., R. 2W., U.S.B.&M

STA: 117+65

DATE: JANUARY 21, 2013




PROJECT VICINITY MAP

PIPE CULVERTS ON UN-NAMED INTERMITTENT STREAM APPLICANT: DUCHESNE COUNTY SHEET NO. 2

SEC. 15, T. 4S., R. 2W., U.S.B.&M

STA: 117+65

DATE: JANUARY 21, 2013







UPSTREAM OF CULVERT



DOWNSTREAM OF CULVERT

PHOTOS

PIPE CULVERTS ON UN-NAMED INTERMITTENT STREAM APPLICANT: DUCHESNE COUNTY

SHEET NO. 4

SEC. 15, T. 4S., R. 2W., U.S.B.&M

STA: 117+65

DATE: JANUARY 21, 2013